

QoS Drive-Test Overview (Barisal Division)

- | | |
|---------------------------|---|
| a. Area: | Barisal, Pirojpur, Jhalokati, Patuakhali, Barguna & Bhola |
| b. Distance Covered (Km): | 1517 (Approx.) |
| c. Drive Test Period: | 21/12/2024 to 31/12/2024 |
| d. No. of Test Days: | 8 |
| e. Findings: | All QoS KPI are BTRC compliant |

KPIs	Benchmarks	Measured value	
Call attempt		3122	
Call attempt failure		18	
Call connected		3104	
Call dropped		0	
Call setup success rate (avg.)	>=97%	99.42%	
Call Drop rate (avg.)	<=2%	0.00%	
Call setup time (avg.)	<= 7 Sec	5.83	
Service Coverage (Avg.)	>= -80 dBm (City Corp Area) >= -90 dBm (Other than City Corp.)	-78.58	
POLQA MOS (avg.)	>= 3.5	3.88	Samples
LTE DL FTP Data Throughput (avg.) (Mbps)	>= 7 Mbps	22.26	3664
LTE UL FTP Data Throughput (avg.) (Mbps)	>= 1 Mbps	13.39	3324

Area map of QoS drive test:

